

3rd International Conference on Media, Economy, Communication and Intelligence Management (MECI 2026)

Article

The Identification and Control Strategies of Quality Risks in Civil Engineering Projects

Dan Wang^{1,*}

¹ College of Management Science and Engineering, China Jiliang University, Hangzhou, China

* Correspondence: Dan Wang, College of Management Science and Engineering, China Jiliang University, Hangzhou, China

Abstract: In civil engineering projects, maintaining high-quality standards throughout all phases, design, construction, and post-construction, is critical to ensuring safety, sustainability, and cost-effectiveness. Quality risks in these projects, including design flaws, material defects, and operational failures, can lead to project delays, cost overruns, and safety hazards. Despite the importance of quality risk management, existing research remains fragmented, focusing on isolated risks within individual stages of the project lifecycle. There is limited attention on integrating risk control measures across all phases and utilizing emerging technologies to improve risk identification and mitigation. This study addresses these gaps by proposing a comprehensive risk management framework that spans the entire lifecycle of civil engineering projects. The research employs case study analysis, literature review, and comparative research to evaluate current risk control measures and identify potential improvements. The study finds that current risk control measures, though effective in some instances, are often fragmented and reactive. It suggests that integrating advanced technologies like Building Information Modeling (BIM), real-time monitoring systems, and predictive analytics could improve risk management and mitigate quality risks across all project stages. This research contributes both theoretically and practically to the field of civil engineering. Academically, it offers a holistic approach to quality risk management. Practically, it provides actionable insights for industry professionals, suggesting improvements in technology integration and collaboration across project stages to enhance project quality, reduce costs, and improve safety.

Keywords: quality risk management; civil engineering; building information modeling; real-time monitoring; predictive analytics

Received: 27 March 2026

Revised: 15 May 2026

Accepted: 28 May 2026

Published: 03 June 2026



Copyright: © 2026 by the authors. Submitted for possible open access publication under the terms and conditions of the Creative Commons Attribution (CC BY) license (<https://creativecommons.org/licenses/by/4.0/>).

1. Introduction

In civil engineering projects, maintaining high quality throughout all stages, from design and construction to operation and maintenance, is crucial for ensuring safety, sustainability, and cost-effectiveness. Quality risks in these projects can manifest in various forms, such as structural failures, material defects, design flaws, and delayed construction timelines. These risks not only threaten the success of individual projects but also impact the broader construction industry by contributing to project cost overruns, rework, and safety hazards [1]. Given the scale and complexity of modern civil engineering projects, effective quality risk management is essential for minimizing potential issues and ensuring successful project delivery.

However, despite the growing importance of quality risk management in civil engineering, research on the identification and control of quality risks remains fragmented. Quality risks differ significantly across project stages, each with its own

unique set of challenges. For example, in the design phase, risks often arise from incorrect specifications or unaddressed structural concerns. During the construction phase, these risks may evolve into issues such as poor workmanship or substandard materials [2]. Finally, post-construction risks can relate to maintenance failures, improper usage, or unforeseen environmental impacts. The existing literature predominantly focuses on isolated risk factors or single-stage interventions, with limited attention given to a comprehensive approach that spans the entire project lifecycle.

This gap in research makes it difficult to assess the cumulative impact of quality risks and the effectiveness of current control strategies across various stages of a civil engineering project. Furthermore, existing risk management frameworks often fail to integrate advanced technologies, such as predictive modeling, real-time monitoring, and data analytics, which could significantly improve risk identification and mitigation efforts. While some research has explored specific risk control measures, such as quality assurance protocols, inspections, and safety audits, these approaches are often reactive rather than proactive, leading to costly interventions after issues have already manifested [1].

This paper aims to address these gaps by proposing a comprehensive framework for the identification and control of quality risks throughout the entire lifecycle of a civil engineering project [1]. The objective is to evaluate current risk control measures, identify their limitations, and suggest improvements that can enhance overall project quality. A key aspect of this study is its emphasis on the integration of innovative techniques and technologies, such as automated quality inspections, machine learning-based predictive models, and real-time project monitoring systems, which can help mitigate risks more effectively at each project stage.

To achieve these objectives, this research will employ a combination of methods, including a detailed literature review, case study analysis, and comparative research [3]. The case study approach will involve an in-depth examination of several large-scale civil engineering projects, focusing on their risk identification and control strategies at different stages. By analyzing both successful and failed projects, this paper will highlight the strengths and weaknesses of current risk management practices. The comparative analysis will also allow for an evaluation of various risk control approaches, providing insights into which strategies are most effective and why.

The significance of this research lies both in its theoretical contributions and its practical applications. Academically, this paper will extend the understanding of quality risk management in civil engineering by developing a more integrated and holistic approach. It will also contribute to the growing body of literature on the application of emerging technologies in risk management [4]. Practically, the findings of this study have the potential to inform industry practices, leading to more effective quality control measures, reduced project delays, lower costs, and improved safety outcomes. By addressing the gaps in current research and offering new strategies for risk mitigation, this study aims to provide valuable insights for both scholars and practitioners in the field of civil engineering.

2. Literature Review

Recent advancements in quality risk management within civil engineering have emphasized the importance of managing risks across various stages of a project, from design through to post-construction. Several studies have focused on identifying, evaluating, and mitigating quality risks, providing valuable insights into the process [5].

Traditional frameworks for quality risk management, such as failure mode and effect analysis (FMEA) and hazard identification, are commonly employed during the design phase to prevent errors in project specifications. Quality assurance (QA) systems and regular inspections during construction help ensure adherence to standards and identify substandard materials or workmanship early. Post-construction, audits and maintenance checks help mitigate long-term risks like material degradation. The integration of technologies such as building information modeling (BIM) and geographic information

systems (GIS) has enhanced risk visualization, allowing for better real-time tracking of progress, materials, and resources, which supports informed decision-making [6].

However, many risk management methods are reactive and stage-specific, rather than comprehensive across the entire project lifecycle. The focus on periodic inspections often fails to anticipate risks before they arise. For example, construction-stage quality assurance can miss issues originating in earlier phases, such as design flaws, which only become apparent during construction [7]. Moreover, the reliance on manual inspections introduces the possibility of human error, undermining the effectiveness of risk control.

Furthermore, risk management strategies often lack integration across stages. Design-phase risk management is disconnected from the construction and maintenance phases, preventing the development of continuous risk identification and mitigation strategies [8]. This fragmentation reduces the overall effectiveness of risk management, as it fails to adapt to emerging risks throughout the project lifecycle.

In comparison to industries like manufacturing or aerospace, which have integrated predictive analytics and automated risk management systems, civil engineering lags behind in adopting advanced technologies. Industries like manufacturing use machine learning and automated monitoring systems for proactive risk management, while civil engineering still relies on manual and reactive measures. This disparity highlights the need for more advanced, data-driven approaches in civil engineering [9].

While existing studies address various risk management techniques, there is a lack of integrated, lifecycle-based frameworks in civil engineering. Research often focuses on individual project stages, neglecting the interconnections between them. Moreover, the potential for advanced technologies, such as real-time monitoring and predictive modeling, to improve risk management has been underexplored, especially in how they can be applied across all stages of a project [1].

This study addresses these gaps by proposing an integrated, lifecycle-based approach to risk management in civil engineering projects. By analyzing case studies and identifying limitations in current practices, the research will highlight how emerging technologies can enhance risk identification, evaluation, and mitigation. The proposed framework aims to bridge the gaps in current risk management strategies and provide a foundation for incorporating advanced technologies into the civil engineering field, contributing both to academic literature and practical industry applications [5].

3. Theoretical Framework and Methodology

This chapter outlines the theoretical framework and research methodology employed in this study to analyze the identification and management of quality risks in civil engineering projects. Through case studies of large-scale projects, this research evaluates the effectiveness of existing quality risk control measures and proposes improvements aimed at enhancing overall project quality [10].

3.1. Theoretical Framework

The theoretical foundation of this study draws from two main frameworks: the Risk Management Process (RMP) and Total Quality Management (TQM). These frameworks provide a structured approach to assessing quality risks throughout the lifecycle of a civil engineering project [11].

RMP involves a systematic approach to identifying, assessing, and mitigating risks in the project lifecycle [12]. It includes five key stages: risk identification, risk assessment, risk control, risk monitoring, and risk review. By following this process, potential quality risks can be identified early, and strategies can be developed to address them proactively before they impact project outcomes. This approach ensures that risk control measures are continually evaluated and refined to keep the project on track.

On the other hand, TQM emphasizes continuous improvement, stakeholder involvement, and a focus on customer satisfaction [13]. TQM principles are applied throughout the project to optimize processes, reduce errors, and maintain high standards of quality. This research adopts the TQM approach to emphasize collaboration and

communication between all parties involved in the project, ensuring that risks are managed effectively across all stages of the project lifecycle.

By integrating these frameworks, this study aims to offer a comprehensive understanding of quality risk management, ensuring that risks are proactively identified and managed throughout the design, construction, and post-construction phases of civil engineering projects [14].

3.2. Methodology

The research utilizes a case study methodology, enabling a detailed examination of real-world projects to identify quality risks at various stages and evaluate the effectiveness of risk control measures. Three large-scale civil engineering projects were selected: a bridge construction project, a high-rise building project, and a road infrastructure project [11]. These projects were chosen based on their complexity, scope, and the variety of risks encountered during different stages, offering a comprehensive perspective on how quality risks arise and are mitigated.

In each project, the following phases were analyzed to identify and address quality risks:

1. Design Phase: This phase often reveals risks such as design flaws, insufficient specifications, and misalignment with client requirements.
2. Construction Phase: Risks during this stage include material defects, workmanship errors, safety violations, and delays.
3. Post-construction Phase: Risks emerging after construction include long-term maintenance challenges, material degradation, and the failure of design assumptions, which may only become apparent once the project is operational.

By analyzing these projects, the research seeks to uncover patterns in quality risk identification and mitigation strategies [14]. The case study approach provides an opportunity to evaluate the practical performance of risk control measures and identify areas for improvement.

3.3. Data Collection and Analysis

Data collection for this study involved several sources: project documentation, stakeholder interviews, and on-site observations. Project documents, such as design specifications, risk management plans, and quality control reports, were reviewed to identify the risk control measures in place at each phase of the projects. Additionally, interviews were conducted with project managers, engineers, and quality control officers to gather insights into their experiences with quality risk management. Finally, site visits allowed for the direct observation of risk control measures in action, particularly during construction and post-construction phases.

The data was analyzed using both qualitative and quantitative methods [3]. Qualitative analysis involved categorizing the risks identified in each phase and evaluating the responses from project stakeholders. Quantitative analysis focused on assessing the impact of risk control strategies by measuring project performance outcomes such as cost overruns, delays, and the number of quality assurance failures.

3.4. Identification and Evaluation of Quality Risks

The case study analysis revealed key quality risks at each project stage, along with the corresponding control measures. During the design phase, one of the most significant risks identified was the occurrence of design errors and omissions. For example, in one project, the initial design did not adequately account for soil conditions, leading to the need for costly foundation redesigns. Additionally, poor communication and coordination between design teams and contractors often led to discrepancies between the design specifications and the final built structure. This issue was further exacerbated by the lack of effective feedback mechanisms between designers and constructors.

During the construction phase, material defects were the most commonly identified risk. In one of the case studies, the use of inferior-grade cement led to concrete cracking shortly after the project was completed, requiring substantial repairs. Furthermore, issues

such as poor workmanship, including improperly installed steel reinforcements and faulty welding, compromised the structural integrity of the building [13]. Safety violations were also a significant risk, with improper scaffolding installation leading to accidents that caused delays in the project timeline.

In the post-construction phase, one of the primary risks identified was material degradation, particularly in road infrastructure projects. The failure to account for environmental conditions during the design phase resulted in accelerated degradation of road surfaces, requiring additional maintenance work within a short period after the project's completion. Moreover, inadequate maintenance planning led to operational failures, such as HVAC system breakdowns in high-rise buildings, which were not detected during initial testing.

In this section, the key quality risks identified across the design, construction, and post-construction phases are summarized in Table 1. The table also provides an evaluation of the current risk control measures in place for each stage and proposes improvements to enhance the effectiveness of these strategies.

Table 1. Key Risks Identified Across Project Stages

Project Stage	Key Risks	Current Risk Control Measures	Proposed Improvements
Design Phase	Design errors, lack of coordination	Design reviews, quality checks	Improved communication between teams, integrated risk systems
Construction Phase	Material defects, workmanship issues, safety	Regular inspections, quality assurance protocols	Adoption of real-time monitoring, use of predictive models
Post-construction	Material degradation, maintenance challenges	Post-construction audits, maintenance checks	Long-term monitoring systems, proactive maintenance planning

3.5. Evaluation of Existing Risk Control Measures

The effectiveness of risk control measures varied across the different stages of the projects [9]. In the design phase, design reviews and quality checks were generally effective at identifying potential risks. However, communication breakdowns between design teams and construction personnel caused misalignments, which undermined the effectiveness of these measures. In the construction phase, regular inspections and third-party quality assurance audits proved beneficial in identifying material defects and workmanship issues. Nevertheless, the reliance on manual inspections often delayed the detection of risks, leading to increased costs and rework.

During the post-construction phase, risk control measures primarily focused on maintenance audits and checks. While these measures helped identify some long-term risks, they were often reactive, addressing issues only after they had already impacted the project. The absence of long-term monitoring systems, such as sensor-based technologies for structural health monitoring, limited the ability to detect potential risks before they escalated [1, 7].

3.6. Proposed Improvements

Based on the findings from the case study analysis, several improvements to existing risk control measures are proposed.

Integrated Risk Management System: Implementing an integrated risk management system across all stages of the project lifecycle would allow for continuous risk identification, assessment, and mitigation [14]. Real-time data collection and analysis should be employed to enhance decision-making and response times.

Adoption of Advanced Technologies: The use of predictive modeling, real-time monitoring systems, and BIM would significantly improve risk identification and control. These technologies can help detect potential risks early and ensure that corrective actions are taken before issues escalate.

Enhanced Communication: Improving communication between design, construction, and maintenance teams is essential for reducing the risk of misalignments and ensuring that quality risks are effectively managed across all stages of the project.

4. Findings and Discussion

4.1. Design Phase Risks and Risk Control Measures

The design phase plays a pivotal role in setting the foundation for the overall quality of a civil engineering project. During this phase, quality risks are often linked to design flaws, errors in calculations, and poor communication between stakeholders. For example, in one case study, a design error occurred when structural load calculations did not consider local soil conditions, leading to structural instability and the need for costly redesigns. This risk could have been identified earlier with better collaboration and more advanced risk identification techniques.

Several risk control measures are employed during the design phase, such as design reviews and peer evaluations, aimed at ensuring that the project meets regulatory and safety standards. However, these measures are often insufficient due to poor communication between design teams and construction contractors, resulting in discrepancies between the design specifications and final execution. Moreover, the absence of advanced technologies like BIM further hinders the visualization of potential design flaws early in the process.

One of the key proposed improvements is the incorporation of BIM for design visualization. BIM creates a digital representation of the project, enabling teams to identify conflicts and design errors before construction begins. Furthermore, adopting integrated project delivery methods can foster better communication and collaboration between design and construction teams, ensuring that the design intent is properly executed. Real-time design reviews, supported by advanced modeling tools, would enhance the efficiency and accuracy of risk control in the design phase.

Figure 1 illustrates the key risk control measures employed during the design phase, highlighting the role of design reviews, peer evaluations, and the integration of BIM for improving risk identification and visualization. The diagram also emphasizes the need for better communication between design and construction teams to avoid discrepancies between the design intent and the final execution.




Figure 1. Risk Control in the Design Phase

4.2. Construction Phase Risks and Risk Control Measures

The construction phase is where quality risks become more tangible, often manifesting as material defects, poor workmanship, safety violations, and delays. In one case study, a batch of concrete used in the foundation did not meet strength specifications, leading to cracks in the structure shortly after construction was completed. This risk could have been identified earlier with more rigorous quality control during the material procurement process.

In this phase, routine inspections, quality assurance audits, and material testing are common practices to identify and mitigate risks. However, in the case studies analyzed, the effectiveness of these measures was compromised by the reliance on manual inspections, which led to delayed identification of risks. This delay, in turn, resulted in rework and increased costs.

One proposed improvement is the integration of real-time monitoring systems, which would allow construction teams to monitor critical factors like temperature, humidity, and concrete curing conditions in real-time. These systems could provide immediate feedback and help identify potential issues before they escalate. Additionally, incorporating predictive analytics and automated inspection systems, such as robotic inspection drones or laser scanning, could improve the speed and accuracy of risk detection, reducing the reliance on manual methods.

Another critical improvement is the enhancement of safety management systems. Wearable technologies, such as smart helmets or sensors, could be used to monitor workers' health and safety in real-time, providing alerts when unsafe conditions are detected. By integrating these technologies into the construction process, not only can worker safety be improved, but quality risks associated with unsafe practices can also be minimized.

4.3. Post-Construction Phase Risks and Risk Control Measures

Post-construction risks typically involve long-term issues such as material degradation, system failures, and inadequate maintenance planning. For instance, HVAC system failures were identified shortly after project completion due to insufficient testing during the construction phase. If left unaddressed, these post-construction risks can result in significant operational challenges and costly repairs.

In many civil engineering projects, post-construction risk control measures emphasize periodic inspections and maintenance schedules [3, 7]. However, in the analyzed case studies, these measures were often reactive. Risks such as material degradation and system malfunctions were addressed only after causing substantial damage, leading to higher repair costs and operational disruptions.

To enhance post-construction risk management, proactive measures such as sensor-based monitoring systems should be adopted. These systems can continuously monitor the condition of building materials, HVAC systems, and other critical infrastructure, providing early warnings of potential failures. Predictive maintenance strategies, utilizing data analytics to forecast maintenance needs, can optimize system performance and minimize downtime [3]. Furthermore, comprehensive long-term monitoring and maintenance protocols would ensure that the project maintains quality standards throughout its operational lifespan.

4.4. Overall Evaluation of Current Risk Control Measures and Proposed Improvements

The case study analysis reveals that current risk control measures are effective but fragmented across project phases. In the design phase, traditional methods like design reviews and regulatory checks are hindered by poor communication and lack of advanced tools such as BIM. Integrating BIM could improve collaboration and reduce misalignments between design and construction.

In the construction phase, while inspections and audits help identify material defects and workmanship issues, manual methods cause delays and increase costs. Real-time monitoring systems using IoT sensors and predictive analytics can detect issues early, while automated inspections, such as drones, can improve accuracy and speed.

Post-construction risks are often reactive due to inadequate maintenance planning. Implementing sensor-based monitoring and AI-driven predictive maintenance would provide real-time data, allowing for proactive interventions and reducing costly repairs.

In summary, integrating technologies such as BIM, real-time monitoring, and predictive maintenance can enhance current risk control measures, leading to better project quality and cost savings [6, 14]. Table 2 evaluates current risk control measures and suggests improvements to better manage risks across all phases.

Table 2. Risk Control Effectiveness and Improvement Strategies

Project Stage	Current Risk Control Techniques	Key Challenges	Proposed Enhancements
Design Phase	Design reviews, regulatory checks, peer evaluations	Poor communication, limited technology use	Incorporate BIM for design visualization, improve collaboration
Construction Phase	Inspections, quality audits, material testing, safety monitoring	Delayed defect identification, manual inspections	Real-time monitoring (IoT), automated inspections (drones), predictive analytics
Post-construction	Performance audits, maintenance checks	Reactive maintenance, failure to address long-term issues	Continuous monitoring, AI-driven predictive maintenance

5. Conclusion

This study provides valuable insights into the identification and management of quality risks in civil engineering projects across different stages, including design, construction, and post-construction. By analyzing case studies and evaluating current risk control measures, this research highlights the challenges faced in each phase and offers practical, technology-driven improvements to enhance project quality and efficiency.

One of the key contributions of this research is the proposal of a more integrated, technology-driven approach to risk management. Current methods, which often rely on manual inspections and reactive measures, are shown to be insufficient for managing risks in modern, complex civil engineering projects. By incorporating advanced technologies such as BIM, real-time monitoring systems, and predictive maintenance powered by AI, risk identification and mitigation can be significantly improved. These technologies enable early detection of potential issues, leading to reduced costs, fewer delays, and better long-term quality management.

From an academic perspective, this study fills gaps in existing literature by offering a comprehensive framework for risk control throughout the entire project lifecycle. It also provides a detailed evaluation of current practices, offering evidence-based suggestions for their enhancement. The integration of technology into risk management practices is not only a theoretical contribution but also a practical one, aligning with current trends in digitization and automation in construction.

Practically, the research offers actionable recommendations for civil engineering professionals, including project managers, contractors, and quality control officers. By adopting the proposed improvements, the construction industry can achieve more efficient, cost-effective, and safer projects.

Future research should focus on further refining these integrated risk management frameworks by exploring the use of emerging technologies, such as machine learning

algorithms for risk prediction and blockchain for transparent project tracking. Additionally, more extensive case studies across different geographic regions and types of projects would provide a broader understanding of the applicability and effectiveness of these risk control measures.

In conclusion, this research provides a solid foundation for improving quality risk management in civil engineering, offering both theoretical insights and practical solutions to enhance the industry's risk control capabilities.

References

1. I. A. Anto, M. J. Gambo, and S. U. Kunya, "Challenges Against Implementation of Quality Control Practices in SUBEB Construction Projects in Bauchi State, Nigeria," *African Journal of Environmental Sciences and Renewable Energy*, vol. 19, no. 1, pp. 244-264, 2025.
2. M. Denman, F. Ullah, S. Qayyum, and O. Olatunji, "Post-construction defects in multi-unit Australian dwellings: an analysis of the defect type, causes, risks, and impacts," *Buildings*, vol. 14, no. 1, p. 231, 2024.
3. O. Alnajjar, E. Atencio, and J. Turmo, "Framework for optimizing the construction process: The integration of Lean Construction, Building Information Modeling (BIM), and emerging technologies," *Applied Sciences*, vol. 15, no. 13, p. 7253, 2025.
4. P. B. Panchal, "Cross-disciplinary risk assessment models for integrated project delivery in large-scale civil engineering projects," 2023.
5. H. M. Jayasinghe, Y. G. Sandanayake, and R. Jayasinghe, "Managing conflicts in joint venture contracts in infrastructure construction projects in Sri Lanka," *Built Environment Project and Asset Management*, vol. 16, no. 2, pp. 415-436, 2026.
6. J. Singh, S. Kumar, and A. Sharma, "Risk assessment and mitigation in construction building projects," *Journal of Construction and Building Materials Engineering*, vol. 11, no. 1, pp. 14-23, 2025.
7. S. Khan, "The application of artificial intelligence and machine learning in civil engineering," *Doupe Journal of Top Trending Technologies*, vol. 1, no. 1, 2025.
8. B. A. Manu, "Innovative construction materials: advancing sustainability, durability, efficiency, and cost-effectiveness in modern infrastructure," *International Journal of Research Publication and Reviews*, vol. 5, no. 12, pp. 4987-4999, 2024.
9. V. Pavate, M. Patil, S. Dharmadhikari, G. Dalavi, S. Sawant, and V. Powar, "A study on factors affecting time, cost and quality in construction project," *International Journal for Research in Applied Science and Engineering Technology*, vol. 12, no. 4, pp. 2627-2635, 2024.
10. A. Pidgeon and N. Dawood, "BIM adoption issues in infrastructure construction projects: analysis and solutions," *Digitalization in Construction*, pp. 173-200, 2023.
11. E. D. Okonta, F. O. Okeke, E. T. Ojelabi, and A. V. Akinola, "Exploring the Role of quality management practices (QMS) in mitigating Construction Failures and building collapse," *Discover Civil Engineering*, vol. 1, no. 1, p. 111, 2024.
12. O. Akindele, S. Ajayi, A. S. Oyegoke, H. A. Alaka, and T. Omotayo, "Application of Geographic Information System (GIS) in construction: a systematic review," *Smart and Sustainable Built Environment*, vol. 14, no. 1, pp. 210-236, 2025.
13. L. I. Qing, L. I. U. Rengkui, Z. Jun, and S. U. N. Quanxin, "Quality risk management model for railway construction projects," *Procedia Engineering*, vol. 84, pp. 195-203, 2014.
14. M. H. Faber and M. G. Stewart, "Risk assessment for civil engineering facilities: critical overview and discussion," *Reliability Engineering & System Safety*, vol. 80, no. 2, pp. 173-184, 2003.

Disclaimer/Publisher's Note: The statements, opinions and data contained in all publications are solely those of the individual author(s) and contributor(s) and not of Publisher and/or the editor(s). Publisher and/or the editor(s) disclaim responsibility for any injury to people or property resulting from any ideas, methods, instructions or products referred to in the content.